

CECW-EG

**DEPARTMENT OF THE ARMY
U.S. Army Corps of Engineers
Washington, DC 20314-1000**

EM 1110-2-2300

Manual
No. 1110-2-2300

30 July 2004

**Engineering and Design
GENERAL DESIGN AND CONSTRUCTION CONSIDERATIONS
FOR EARTH AND ROCK-FILL DAMS**

Subject	Paragraph	Page
Chapter 1 Introduction		
Purpose.....	1-1	1-1
Applicability	1-2	1-1
References.....	1-3	1-1
Overview of Manual	1-4	1-1
Chapter 2 General Considerations		
General.....	2-1	2-1
Civil Works Project Process	2-2	2-2
Types of Embankment Dams.....	2-3	2-3
Basic Requirements	2-4	2-5
Selection of Embankment Type.....	2-5	2-7
Environmental Considerations.....	2-6	2-8
Chapter 3 Field Investigations and Laboratory Testing		
Geological and Subsurface Explorations and Field Tests.....	3-1	3-1
Laboratory Testing.....	3-2	3-4
Chapter 4 General Design Considerations		
General.....	4-1	4-1
Freeboard	4-2	4-3
Top Width	4-3	4-3
Alignment	4-4	4-3
Embankment	4-5	4-3
Abutments	4-6	4-3
Performance Parameters	4-7	4-4
Earthquake Effects	4-8	4-5
Coordination Between Design and Construction.....	4-9	4-5
Value Engineering Proposals	4-10	4-6
Partnering Between the Owner and Contractor	4-11	4-6

Subject	Paragraph	Page
Modifications to Embankment Dams to Accommodate New or Revised Inflow Design Floods or to Provide Additional Storage for Water Supply or Other Purposes.....	4-12	4-7
Chapter 5		
Foundation and Abutment Preparation		
Preparation	5-1	5-1
Strengthening the Foundation	5-2	5-3
Dewatering the Working Area	5-3	5-3
Chapter 6		
Seepage Control		
General.....	6-1	6-1
Embankment	6-2	6-1
Earth Foundations	6-3	6-1
Rock Foundations	6-4	6-5
Abutments	6-5	6-6
Adjacent to Outlet Conduits.....	6-6	6-6
Beneath Spillways and Stilling Basins.....	6-7	6-6
Seepage Control Against Earthquake Effects	6-8	6-7
Chapter 7		
Embankment Design		
Embankment Materials	7-1	7-1
Zoning.....	7-2	7-2
Cracking.....	7-3	7-3
Filter Design.....	7-4	7-8
Consolidation and Excess Porewater Pressures	7-5	7-8
Embankment Slopes and Berms	7-6	7-9
Embankment Reinforcement	7-7	7-9
Compaction Requirements.....	7-8	7-10
Slope Protection.....	7-9	7-14
Chapter 8		
Appurtenant Structures		
Outlet Works.....	8-1	8-1
Spillway	8-2	8-1
Other Important Considerations.....	8-3	8-2
Chapter 9		
General Construction Considerations		
General.....	9-1	9-1
Obtaining Quality Construction	9-2	9-1
Stage Construction	9-3	9-2
Stream Diversion	9-4	9-2
Closure Section	9-5	9-3
Construction/Design Interface	9-6	9-4
Visual Observations	9-7	9-4
Compaction Control.....	9-8	9-4

Subject	Paragraph	Page
Initial Reservoir Filling.....	9-9	9-5
Construction Records and Reports.....	9-10	9-6

Chapter 10
Instrumentation

General.....	10-1	10-1
Instrumentation Plan and Records	10-2	10-1
Types of Instrumentation	10-3	10-3
Discussion of Devices.....	10-4	10-3
Measurements of Seepage Quantities	10-5	10-4
Automated Data Acquisition Systems	10-6	10-4

Appendix A
References

Appendix B
Filter Design

Appendix C
Slope Protection

Appendix D
Automatic Data Acquisition Systems

Appendix E
Process for Establishing Performance Parameters

Appendix F
Methods of Dam Raising

